

DEFENSE INFORMATION SYSTEMS AGENCY

P. O. BOX 549 FORT MEADE, MARYLAND 20755-0549

 $\frac{\text{IN REPLY}}{\text{REFER TO:}}$ Joint Interoperability Test Command (JTE)

30 Nov 12

MEMORANDUM FOR DISTRIBUTION

SUBJECT: Extension of the Special Interoperability Test Certification of the Cisco Catalyst 4500E Series with Supervisor Engine 7L-E (Sup7L-E) Switch Release Update from IOS XE 3.3(0)SG to 3.3(1)SG

References: (a) Department of Defense (DoD) Directive 4630.05, "Interoperability and Supportability of Information Technology (IT) and National Security Systems (NSS)," 5 May 2004

- (b) Chairman, Joint Chiefs of Staff Instruction (CJCSI) 6212.01E, "Interoperability and Supportability of Information Technology and National Security Systems," 15 December 2008
- (c) through (e), see Enclosure 1
- 1. References (a) and (b) establish the Defense Information Systems Agency (DISA), Joint Interoperability Test Command (JITC), as the responsible organization for interoperability (IO) test certification.
- 2. The Cisco WS-C4507R+E with Sup7L-E Switch Release IOS XE 3.3(0)SG is hereinafter referred to as the System Under Test (SUT). The SUT meets all of its critical IO requirements and is certified for joint use within the Defense Information System Network (DISN) as an Assured Services Local Area Network (ASLAN) Layer 2 Access switch. The SUT is certified as interoperable for joint use with other ASLAN components listed on the Unified Capabilities (UC) Approved Products List (APL) with the following interfaces: 10/100/1000BaseT and 100/1000BaseX for access, 1000BaseT and 1000/10000BaseX for uplink. All of these interfaces were tested with the exception of the 10BaseT interface. JITC analysis determined that the 10BaseT interface is a low risk for certification based on the vendor's Letter of Compliance (LoC) to comply with the Institute of Electrical and Electronics Engineers (IEEE) 802.3i standard and the testing data collected at all other data rates. The SUT meets the critical IO requirements set forth in Reference (c), using test procedures derived from Reference (d). The Cisco WS-C4503-E, WS-C4506-E, and WS-C4507R-E switches with Sup7L-E employ the same software and similar hardware as the SUT. JITC analysis determined these systems to be functionally identical to the SUT for IO certification purposes, and they are also certified for joint use.

The SUT is certified to support Assured Services within an ASLAN. If a component meets the minimum requirements for deployment in an ASLAN, it also meets the lesser requirements for deployment in a non-ASLAN. Non-ASLANs are "commercial grade" and provide support to Command and Control (C2) (ROUTINE only calls) (C2(R)) or non-C2 voice subscribers. When deployed in a non-ASLAN, the SUT may also be used to receive all levels of precedence, but is

JITC Memo, JTE, Extension of the Special Interoperability Test Certification of the Cisco Catalyst 4500E Series with Supervisor Engine 7L-E (Sup7L-E) Switch Release Update from IOS XE 3.3(0)SG to 3.3(1)SG

limited to supporting calls that are originated at ROUTINE precedence only. Non-ASLANs do not meet the availability or redundancy requirements for C2 or Special C2 users and therefore are not authorized to support precedence calls originated above ROUTINE.

Testing of the SUT did not include video services or data applications; however, simulated video traffic, preferred data, and best effort data were generated during testing to determine the SUT's ability to prioritize and properly queue voice media and signaling traffic. No other configurations, features, or functions, except those cited within this document, are certified by JITC. This certification expires upon changes that affect IO but no later than three years from the date of the UC APL memorandum, 12 September 2012.

- 3. The extension of this certification is based upon Desktop Review (DTR) 1. The original certification is based on IO testing conducted by the United States Army Information Systems Engineering Command, Technology Integration Center (USAISEC TIC), review of the vendor's LoC, DISA adjudication of open test discrepancy reports (TDRs), and the DISA Certifying Authority (CA) Recommendation. The IO testing was conducted by the USAISEC TIC, Fort Huachuca, Arizona, from 7 May through 15 June 2012. Review of the vendor's LoC was completed on 17 July 2012. DISA's adjudication of outstanding TDRs was completed on 7 August 2012. The DISA CA provided a positive recommendation on 25 August 2012, based on the security testing completed by USAISEC TIC-led Information Assurance (IA) test teams. Those test results are published in a separate report, Reference (e). This DTR was requested to update Cisco IOS Release 3.3.(0)SG to 3.3.(1)SG. JITC determined there was minor risk in approving DTR1 without interoperability testing because the IOS update includes maintenance upgrades that do not include any hardware or software feature upgrades, therefore, do not change the interoperability results. DTR 1 has no impact on the approved IA posture, so the original CA approval date still applies. Therefore, JITC approves this DTR.
- 4. Table 1 provides a UC APL product summary. Table 2 provides the SUT interface IO status and Table 3 provides the Capability Requirements (CRs) and Functional Requirements (FRs) status. The threshold CRs/FRs for ASLAN components are established by Section 5.3.a of Reference (c) and were used to evaluate the IO of the SUT. Enclosure 3 provides a detailed list of the interface, capability, and functional requirements.

Table 1. UC APL Product Summary

Component 1	Release	Sub-Component ¹	Certification Applicability			
Component	Release	Sub-Component	Core Distribu		Access	
WS-C4507R+E WS-C4503-E WS-C4506-E WS-C4507R-E	IOS XE 3.3.(1)SG	WS-X45-Sup7L-E, WS-X4712-SFP+E, WS-X4748- RJ45V+E, WS-X4640-CSFP-E, WS-X4606-X2-E, WS-X4648-RJ45V+E, WS-X4548-RJ45V+, WS- X4748-RJ45-E, WS-X4748-UPOE+E, WS-X4648- RJ45-E, WS-X4548-GB-RJ45V, WS-X4548-GB-RJ45 WS-X4624-SFP-E ² , WS-X4612-SFP-E ² , WS-X4248- FE-SFP ² , WS-X4148-FX-MT ² , WS-X4448-GB-SFP ²	N/A	N/A	Yes	

JITC Memo, JTE, Extension of the Special Interoperability Test Certification of the Cisco Catalyst 4500E Series with Supervisor Engine 7L-E (Sup7L-E) Switch Release Update from IOS XE 3.3.(0)SG to 3.3.(1)SG

Table 1. UC APL Product Summary (continued)

NOTE:

- 1. Components bolded and underlined were tested by the USAISEC TIC. The other components in the family series were not tested; however, they utilize the same OS software and similar hardware. JITC analysis determined them to be functionally identical for IO certification purposes and they are also certified for joint use.
- 2. These modules are certified based upon test data collected during previous ASLAN certification test events; no changes to modules or hardware and no changes to the requirements since modules were last tested and certified.

LEGEND:

APL Approved Products List N/A Not Applicable ASLAN Assured Services Local Area Network OS Operating System

IO Interoperability TIC Technology Integration Center

IOS Internetworking Operating System UC Unified Capabilities

JITC Joint Interoperability Test Command UCR Unified Capabilities Requirements

L2 Layer 2 USAISEC U.S. Army Information Systems Engineering Command

Table 2. SUT Interface Interoperability Status

Interface	Applicability			UCR 2008, Change 3	Threshold	Status	Remarks	
Interface	Co	D	A	Reference	CR/FR ¹	Status	Kemai Ks	
Serial	С	С	С	5.3.1.3.9	1-4	Certified	The SUT met the CRs and FRs with the following standard: EIA-232.	
10Base-X	С	С	\mathbb{C}^2	5.3.1.3.1	1-6	Certified ³	The SUT met CRs and FRs with the following IEEE standard: 802.3i (10BaseT).	
100Base-X	R	R	\mathbb{C}^2	5.3.1.3.1	1-6	Certified	The SUT met CRs and FRs with the following IEEE standard: 802.3u (100BaseT/F).	
1000Base-X	R	R	\mathbb{C}^2	5.3.1.3.1	1-6	Certified	The SUT met CR and FRs with the following IEEE standards: 802.3ab (1000BaseT), 802.3z (1000Base-SX, 1000Base-LX).	
10000Base-X	С	С	С	5.3.1.3.1	1-6	Certified	The SUT met CRs and FRs with the following IEEE standard: 802.3ae (10GBase-SR, 10GBase-LR).	
802.11a	С	С	С	5.3.1.3.1/5.3.1.7.2	1-6	Not Supported ⁴	N/A	
802.11b	С	С	С	5.3.1.3.1/5.3.1.7.2	1-6	Not Supported ⁴	N/A	
802.11g	С	С	С	5.3.1.3.1/5.3.1.7.2	1-6	Not Supported ⁴	N/A	
802.11n	С	С	С	5.3.1.3.1/5.3.1.7.2	1-6	Not Supported ⁴	N/A	
802.16	C	C	C	5.3.1.3.1/5.3.1.7.2	1-6	Not Supported ⁴	N/A	

NOTES

- 1. The SUT high-level CR and FR ID numbers depicted in the Threshold CRs/FRs column can be cross-referenced in Table 3. These high-level CR/FR requirements refer to a detailed list of requirements provided in Enclosure 3.
- 2. Core and Distribution products must minimally support 100Base-X (802.3u) and 1000Base-X (802.3z). Access products must minimally support one of the following standards: 802.3i (10BaseT), 802.3j (10BaseF), 802.3u (100BaseT/F), 802.3z (1000BaseF), or 802.3ab (1000BaseT). Other rates and standards may be provided as conditional interfaces.
- 3. The USAISEC TIC tested all these interfaces with the exception of the 10BaseT interface. JITC analysis determined that the 10BaseT interface is a low risk for certification based on the vendor's LoC to the IEEE 802.3i and the testing data collected at all other data rates.
- 4. The SUT does not support this interface. This interface is not required for a Core, Distribution, or Access switch.

JITC Memo, JTE, Extension of the Special Interoperability Test Certification of the Cisco Catalyst 4500E Series with Supervisor Engine 7L-E (Sup7L-E) Switch Release Update from IOS XE 3.3(0)SG to 3.3(1)SG

Table 2. SUT Interface Interoperability Status (continued)

LEGEND:			
802.3ab	1000BaseT Gbps Ethernet Over Twisted Pair at	C	Conditional
	1Gbps (125 Mbps)	Co	Core
802.3ae	10 Gbps Ethernet	CR	Capability Requirement
802.3i	10BaseT Mbps Over Twisted Pair	D	Distribution
802.3j	10 Mbps Over Fiber	EIA	Electronic Industries Alliance
802.3u	Standard for Carrier Sense Multiple Access with	EIA-232	Standard for Defining the Mechanical and Electrical
	Collision Detection at 100 Mbps		Characteristics for Connecting Data Terminal Equipment
802.3z	Gigabit Ethernet Standard		(DTE) and Data Circuit-Terminating Equipment (DCE)
802.11/16	IEEE Wireless Standards		Data Communications Devices
10BaseF	10 Mbps Ethernet Over Fiber	FR	Functional Requirement
10BaseT	10 Mbps (Baseband Operation, Twisted Pair)	Gbps	Gigabits Per Second
	Ethernet	ID	Identification
10Base-X	10 Mbps Ethernet Over Fiber or Copper	IEEE	Institute of Electrical and Electronics Engineers
100BaseF	100 Mbps Ethernet Over Fiber	JITC	Joint Interoperability Test Command
100BaseT	100 Mbps (Baseband Operation, Twisted Pair)	LoC	Letter of Compliance
	Ethernet	LR	Long Range Optics
100Base-X	100 Mbps Ethernet Over Fiber or Copper	LX	Single-Mode Fiber Optics
1000BaseF	1000 Mbps Ethernet Over Fiber	Mbps	Megabits Per Second
1000Base-LX	1000 Mbps Ethernet Over Fiber	N/A	Not Applicable
1000Base-SX	1000 Mbps Ethernet Over Fiber	R	Required
1000BaseT	1000 Mbps (Baseband Operation, Twisted Pair)	SR	Short Range Optics
	Ethernet	SX	Multi-Mode Fiber Optics
1000Base-X	1000 Mbps Ethernet Over Fiber or Copper	SUT	System Under Test
10000Base-X	10000 Mbps Ethernet Over Fiber or Copper	TIC	Technology Integration Center
10GBase-LR	10000 Mbps Ethernet Over Fiber	UCR	Unified Capabilities Requirements
10GBase-SR	10000 Mbps Ethernet Over Fiber	USAISEC	
A	Access		

JITC Memo, JTE, Extension of the Special Interoperability Test Certification of the Cisco Catalyst 4500E Series with Supervisor Engine 7L-E (Sup7L-E) Switch Release Update from IOS XE 3.3.(0)SG to 3.3.(1)SG

Table 3. SUT CRs and FRs Status

CR/FR ID	Capability/Function	Applicability ¹	UCR 2008, Change 3 Reference	Status	Remarks				
	General Performance Parameters								
1	Performance Parameters	Required	5.3.1.3	Partially Met					
	Port Interface Rates	Required	5.3.1.3.1	Met					
	Port Parameter Requirements	Required	5.3.1.3.2	Met					
	Class of Service Markings	Required	5.3.1.3.3	Met					
	VLAN Capabilities	Required	5.3.1.3.4	Met					
	Protocols	Required	5.3.1.3.5	Met					
	QoS Features	Required	5.3.1.3.6	Met					
	Network Monitoring	Required	5.3.1.3.7	Met					
	Security	Required	5.3.1.3.8	Met					
	E2E Performance Requirements								
2	Voice Services	Required	5.3.1.4.1	Met ²					
Z	Video Services	Required	5.3.1.4.2	Met ²					
	Data Services	Required	5.3.1.4.3	Met ²					
	NM Requirements								
	Configuration Control	Required	5.3.1.6.1	Met					
	Operational Changes	Required	5.3.1.6.2	Met					
3	Performance Monitoring	Required	5.3.1.6.3	Met					
	Alarms	Required	5.3.1.6.4	Met					
	Reporting	Required	5.3.1.6.5	Met					
	Engineering Requirements								
4	Physical Media	Required	5.3.1.7.1	Met ³					
	Wireless	Conditional	5.3.1.7.2	Not Tested ⁴					
7	Traffic Engineering	Required	5.3.1.7.3	Met ³					
	Availability	Required	5.3.1.7.6	Met ³					
	Redundancy	Required	5.3.1.7.7	Met ³					
5	MPLS								
	MPLS Requirements	Conditional	5.3.1.8.4.1	Not Tested ⁴					
	MPLS VPN Augmentation to VLANs	Conditional	5.3.1.8.4.2	Not Tested ⁴					
(IPv6 Requirements								
6	Product Requirements	Required	5.3.5.4	Met					

JITC Memo, JTE, Extension of the Special Interoperability Test Certification of the Cisco Catalyst 4500E Series with Supervisor Engine 7L-E (Sup7L-E) Switch Release Update from IOS XE 3.3(0)SG to 3.3(1)SG

Table 3. SUT CRs and FRs Status (continued)

NOTES:

- 1. The annotation of 'Required' refers to a high-level requirement category. The applicability of each sub-requirement is provided in Enclosure 3. The SUT does not need to provide conditional requirements. However, if a capability is provided, it must function according to the specified requirements.
- 2. This requirement was verified and met using simulated voice, video, and data traffic in an operational emulated environment to meet E2E requirements. The SUT must be deployed IAW deployment guide and engineering guidelines in UCR 2008, Change 3, Section 5.3.1.4.
- 3. This requirement was met with the following stipulations: It is the site's responsibility to configure the SUT in a manner which meets the engineering requirements listed in Section 11.2 d. of Enclosure 2, and that it does not create a single point of failure which could impact more than 96 C2 users
- 4. Wireless and MPLS were not tested and are not certified for joint use. Wireless and MPLS are conditional and; therefore, not required for a Core, Distribution, or Access switch.

LEGEND:

LEGEN	D.		
C2	Command and Control	MPLS	Multiprotocol Label Switching
CR	Capability Requirement	NM	Network Management
E2E	End-to-End	QoS	Quality of Service
FR	Functional Requirement	SUT	System Under Test
ID	Identification	UCR	Unified Capabilities Requirements
IAW	In Accordance With	VLAN	Virtual Local Area Network
IPv6	Internet Protocol Version 6	VPN	Virtual Private Network

5. In accordance with the Program Manager's request, no detailed test report was developed. JITC distributes IO information via the JITC Electronic Report Distribution (ERD) system, which uses Unclassified-But-Sensitive Internet Protocol Router Network (NIPRNet) e-mail. More comprehensive IO status information is available via the JITC System Tracking Program (STP), which is accessible by .mil/.gov users on the NIPRNet at https://stp.fhu.disa.mil. Test reports, lessons learned, and related testing documents and references are on the JITC Joint Interoperability Tool (JIT) at http://jit.fhu.disa.mil. (NIPRNet). Information related to DISN testing is on the Telecom Switched Services Interoperability (TSSI) website at http://jitc.fhu.disa.mil/tssi. All associated data is available on the DISA Unified Capability Coordination Office (UCCO) website located at http://www.disa.mil/ucco/. Due to the sensitivity of the information, the Information Assurance Accreditation Package (IAAP) that contains the approved configuration and deployment guide must be requested directly from U.S. Government civilian or uniformed military personnel at the UCCO; e-mail: http://jitc.fhu.disa.mil/ucco/. Report of the sensitivity of the information and deployment guide must be requested directly from U.S. Government civilian or uniformed military personnel at the UCCO; e-mail: http://jitc.fhu.disa.mil.

JITC Memo, JTE, Extension of the Special Interoperability Test Certification of the Cisco Catalyst 4500E Series with Supervisor Engine 7L-E (Sup7L-E) Switch Release Update from IOS XE 3.3.(0)SG to 3.3.(1)SG

6. The testing point of contact Mr. James Hatch, DSN 821-2860, commercial (520) 533-2860, or email to james.d.hatch12.civ@mail.mil. The JITC point of contact is Ms. Anita Mananquil, DSN 879-5164, commercial (520) 538-5165, FAX DSN 879-4347, commercial (520) 538-4347, or email to anita.l.mananquil.civ@mail.mil. JITC's mailing address is P.O. Box 12798, Fort Huachuca, AZ 85670-2798. The Tracking Number for the SUT is 1126909.

FOR THE COMMANDER:

Enclosure a/s

for BRADLEY A. CLARK

T. Schutto

Acting Chief

Battlespace Communications Portfolio

DISTRIBUTION (electronic mail):

DoD CIO

Joint Staff J-6, JCS

USD(AT&L)

ISG Secretariat, DISA, JTA

U.S. Strategic Command, J665

US Navy, OPNAV N2/N6FP12

US Army, DA-OSA, CIO/G-6 ASA(ALT), SAIS-IOQ

US Air Force, A3CNN/A6CNN

US Marine Corps, MARCORSYSCOM, SIAT, A&CE Division

US Coast Guard, CG-64

DISA/TEMC


DIA, Office of the Acquisition Executive

NSG Interoperability Assessment Team

DOT&E, Netcentric Systems and Naval Warfare

Medical Health Systems, JMIS IV&V

Defense Information Systems Agency, GS23



ADDITIONAL REFERENCES

- (c) Office of the DoD Chief Information Officer, "Department of Defense Unified Capabilities Requirements 2008 (UCR 2008), Change 3," September 2011.
- (d) Joint Interoperability Test Command, "ASLAN Component Test Plan (UCTP)," February 2012.
- (e) U.S. Army Information Systems Engineering Command, Technology Integration Center (USAISEC TIC), "Information Assurance (IA) Assessment of Cisco Catalyst 4500E Series with Supervisor Engine 7L-E (Tracking Number 1126909)," 3 August 2012.